

NAME OF WORK :- CONSTRUCTION OF COMPOUND WALL TO POULTRY FARM AT P.G.I.V.A.S. AKOLA

SCHEDULE - B & C

Sr. No.	Qty.	Description of Item	Rates		Unit	Amount	Ref. To Std. Sr. No. & Page No.
			In Figure (Rs.)	In words			
1	108.00	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area & stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting CSR- p.no.7/i.no.1	120.69	Rs.One hundred twenty and sixty nine paisa only	one cubic meter	13035.00	Bd A.1 P. No. 259
2	18.00	Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with sand / grit ramming, watering complete. Spec. No. : As directed by Engineer in charge. p.no.3/i.no.10	737.53	Rs.Seven hundred thirty seven and fifty three paisa only	one cubic meter	13276.00	10 BDA 14
3	9.00	Providing and laying in situ, cement concrete in M-10 of	3139.45	Rs.Three thousand one hundred	one cubic	28255.00	3 BDE 1A

		trap/granite/quartzite/gneiss metal for foundation and bedding including bailing out water, formwork, compacting and curing complete. Spec. No.: BDE. 1A Page No. 287 p.no.7/i.no.3		thirty nine and fourty five paisa only	meter		
4	84.38	Providing uncoursed rubble masonry of trap/ granite/quartzite/gneiss stones in cement mortar 1:6 in foundation and plinth of inner walls/in plinth of external walls including bailing out water, striking joints on un exposed faces and watering complete. CSR- p.no.20/i.no.1	1708.83	Rs.One thousand seven hundred eight and eighty three paisa only	one cubic meter	144191.00	Bd.H. 1 Page No. 329
5	10.57	Providing and casting in situ cement concrete in M-15 of trap/ granite/ quartzite/ gneiss metal for R.C.C.coping to plinth or parapet amd sill of doors and windows moulded as per detailed drawings or chamfered as approved by the Engineer including centering, formwork, cover blocks, compacting and roughening them if special finish is to be provided and curing complete. (Excluding reinforcement). CSR- p.no.8/i.no.6	4440.45	Rs. Four thousand four hundered forty and forty five paisa only	one cubic meter	46936.00	Bd.E.3/P. 288 I.S.456(2000)
6	0.95	Providing and fixing in position HYSD reinforcement of various diameters for R.C.C. pile caps, footings, foundations,	64019.50	RsSixty four thosand ninteen and fifty paisa	one metric tone	60819.00	Bd.F.17 P. 306

		slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete. Spec No: p.no.18/i.no.8		only			
7	180.00	Providing flush grooved pointing with cement mortar 1:3 for stone masonry including scaffolding and curing complete. CSR - p.no.36/i.no.26	74.35	Rs. Seventy four and thirty five paisa only	one square meter	13383.00	Bd.L.15 P. 372
8	54.79	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding Complete. CSR - p.no.17/i.no.3	4865.39	Rs. Four thousand eight hundred sixty five and thirty nine paisa only	one cubic meter	266575.00	Bd.G.5/ P. 315
9	593.18	Providing sand faced plaster externally in cement mortar using approved screened sand in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 Kg. per cement bag curing the same for not less than 2 days	353.08	Rs. Three hundred fifty three and eight paisa only	one square meter	209440.00	Bd.L.7 P. 369

